



### **Fencing Bid**

The Town of Eagar is seeking bids to have a contractor construct and install approximately 2,850 linear feet of stamped concrete fence with columns and an additional 350 linear feet of fence on the west side of the location that utilize the same columns, but with two-foot-tall concrete panels and 4-foot-tall wrought iron fence panels installed on top of the two-foot concrete panels. This fence will consist of stamped concrete columns, approximately 20" wide x 20" deep x 72" tall, placed on top of concrete piers and 6-foot-tall stamped concrete panels inserted between the columns with 22" x 22" capstones placed on top of each of the columns. Please see pictures below.





Measure distance  
 Total area: 397,497.79 ft² (36,928.75 m²)  
 Total distance: 3,165.92 ft (964.97 m)